



(An Autonomous Institution Under MHRD, Government of India)
Melakkottaiyur, Off Vandalur-Kelambakkam Road, Chennai – 600127.

Ph: +9144 2747 6322/6324

Email: estate@iiitdm.ac.in

No. IIITDM/19/2020/Medical Care Unit/104.

Date: 17 Feb 2020

NOTICE INVITING QUOTATION (NIQ)

The Registrar, IIITDM Kancheepuram invites sealed quotations for the following work so as to be reach this office on or before ~~21-02-2020~~ ^{24/02/2020 Ad} at 15.00 hrs, the same will be opened before the intending quotationers on the same day at 15.30 hrs.

| Sl. No | Description of items | Qty | Rate in Words | Rate in figures | Unit | Amount in Rs. |
|--------|---|-----|---------------|-----------------|------|----------------|
| 1. | FACELIFTING OF THREE EXISTING ROOMS IN BANYAN HOSTEL ROOM NO.2,3 &4 INTO MEDICAL CARE UNIT AT IIITDM KANCHEEPURAM | | | | | Ref. Annex - 1 |

The rate quoted shall be net inclusive of all taxes, transportation, men, material, machinery, equipment. Nothing extra shall be payable under any account over and above the rate quoted.


Registrar
IIITDM Kancheepuram

General Terms and Conditions:

1. The quotations should be valid for 30 days from the due date and this work needs to be carried out in a time bound manner and the entire work including providing, placing, lifting, fixing in position, installation, testing, commissioning in all lead in the address/ area mentioned above of this Institute and the work shall be completed within 15 days from the date of issue of work order.
2. Any delay in commissioning the work on the time and date mentioned in sl.no. 1 will lead to the total rejection of the work and no payment whatsoever shall be made towards the work.
3. The electricity/water for the work will be supplied free of cost by the Institute. However suitable tapping of power (**appropriate cable, extension boards etc**) for the designated outlet for each work shall be the responsibility of the vendor of the work.
4. **The vendor shall take care of all safety and precautionary measures during material supply, installation, erection, commissioning and running the said work. The work shall be carried out as per the safety norms and regulation of state and central Electricity Act.**
5. No damage shall be made to any of the institute's buildings, equipments, fittings, surfaces, painting etc. If any made shall be restored by the vendor at his own cost.
6. On completion of work the vendor at his own cost remove all the temporary fixtures, waste materials, un wanted items and remove the entire un wanted materials within 24 hours after completion of this work.
7. The vendor shall be responsible for any misuse of power/water and institute equipments by his employee or representative. The care shall be taken to utilize the institute belongings given for this purpose for its bonafide use only.
8. No unsolicited correspondence shall be entertained after the submission of the quotation.
9. Quoting merely the lowest price does not confer any right to any bidder for award of work order. The Institute reserves the right to select any bid on the grounds of quality of previous works, past experience, offer of additional/special features, compatibility etc.

10. The Engineer Incharge also reserves the right to reject any bids with sub-standard products even if they are found to be lowest.
11. All the electrical/ Civil and other items should be complied with ISI standard.
12. The quotations duly sealed and super scribed on the envelope with the reference no. and due date, should be addressed to the undersigned so as to reach him on or before the due date stipulated above.
13. The rate quoted should be inclusive of all material, tools, labour, transportation and installations etc complete.
14. Special concession in rates if any applicable for Educational Institution shall also be offered and indicated clearly.
15. Penalty for delayed services / LD
 - (i) As time is essence of the contract, the period of work mentioned in the work order should be strictly adhered to.
 - (ii) If the vendor fails to perform the work as per the specifications mentioned in the order within the due date and time the vendor is liable to pay liquidated damages of 10% of work order value and the work will be executed through some other Agency at the risk and cost of the vendor.
16. Statutory GST will be reimbursed only on production of paid voucher. Statutory tax deduction (TDS) will be made from the value of work done.
17. The IIITDM kancheepuram reserves the right to accept the offer in full or in parts or reject the offer summarily or partly without assigning any reasons.
18. The payment shall be made as first and final bill on satisfactorily completion of the work. The payment shall be based on the actual measurement taken by the engineer in-charge.
19. Any less usage of number of items/work the rate will be reduced pro-rata and vice versa.


Registrar,
IIITDM Kancheepuram

ANNEXURE - 1

| NAME OF THE WORK: FACELIFTING OF THREE EXISTING ROOMS IN BANYAN HOSTEL ROOM NO.2,3 &4 INTO MEDICAL CARE UNIT AT IIITDM KANCHEEPURAM | | | | | |
|--|---|------------|-------------|-------------|----------------------|
| Sl.No | Description of the Item | Qty | Unit | Rate | Amount in Rs. |
| 1 | Taking out doors, windows and clerestory window shutters (steel or wood) including stacking with 50 meters lead: | | | | |
| 1.1 | Of area 3 Sq. meters and below | 1 | Each | | |
| 2 | Demolishing brick work manually /by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge | 2 | Cum | | |
| 2.1 | In cement mortar | | | | |
| 3 | Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber. Neoprene gasket, etc. Aluminum sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing/paneling, C.P. brass/stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): | | | | |
| 3.1 | For fixed portion (Frame) | | | | |
| 3.1.2 | Anodized aluminum (anodized transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade Ac 15) | 20 | Kg | | |
| 4 | For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/neoprene gasket required (Fittings shall be paid for separately) | | | | |
| 4.1 | Anodized aluminum (anodized transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade Ac 15) | 15 | Kg | | |
| 5 | Providing and fixing 12mm thick pre laminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade I Type II, in paneling fixed in aluminum doors, windows shutters and partition frames with | | | | |

| | | | | | |
|------|---|-----|------|--|--|
| | C.P. Brass/stainless steel screws, etc., complete as per architectural drawings and directions of engineer-in-charge. | | | | |
| 5.1 | Pre-laminated particle board with decorative lamination on both sides | 3 | Sq.m | | |
| 6 | Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc., with EPDM rubber/neoprene gasket etc., complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminum snap beading shall be paid in basic item): | | | | |
| 6.1 | With float glass panes of 5.50mm thickness | 3 | Sq.m | | |
| 7 | Brick work with common burnt clay F.P.S (non modular)bricks of class designation 7.5 in foundation and plinth in : | | | | |
| 7.1 | Cement mortar 1:6 (1 cement : 6 coarse sand) | 1 | Cum | | |
| 8 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-All work up to plinth level: | | | | |
| 8.1 | 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) | 9 | Cum | | |
| 9 | 12mm cement plaster of mix: | | | | |
| 9.1 | 1:6 (1 cement : 6 fine sand) | 3 | Sq.m | | |
| 10 | Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 Sq. meters and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 meters lead : | | | | |
| 10.1 | With cement mortar 1:4 (1 cement : 4 fine sand) | 4 | Sq.m | | |
| 11 | Half brick masonry with common burnt clay F.P.S (non modular bricks of class designation 7.5 in foundations and plinth in. | | | | |
| 11.1 | Cement mortar 1:4 (1 cement : 4 coarse sand) | 5 | Sq.m | | |
| 12 | Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc., in layers not exceeding 20cm in depth ,consolidating each deposited layer by ramming and watering, lead up to 50m and lift up to 1.5m. | 11 | Cum | | |
| 13 | Distempering with oil bound washable distemper of approved brand and manufacture to give na even shade: | | | | |
| 13.1 | Old work (one or more coats) | 170 | Sq.m | | |
| 14 | Painting with synthetic enamel paint of approved brand and manufacture of required color to give an even shade: | | | | |
| 14.1 | One or more coats on old work | 10 | Sq.m | | |
| 15 | Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required color and pattern over and including 50mm thick compacted bed of fine sand, filling the joints with coarse sand etc., all complete as per the direction of Engineer-in-charge | 90 | Sq.m | | |

| | | | | | |
|--------------|--|----|------|--|--|
| 16 | Providing and fixing S.S. Pipe curtain roads with SS brackets: | | | | |
| 16.1 | 25mm dia (heavy type) | 30 | Mtr | | |
| 17 | Providing and fixing door closer ISI marked | 1 | each | | |
| 18 | Providing and placing Precast RCC lintels of size 1300mmx230mmx150mm made of RCC mix of 1:1.5:3 including providing reinforcement of 4 nos 12mm dia TMT main bars and stirrups of 8mm dia TMT bars etc., complete as directed by the Engineer-in-charge. | 2 | Nos | | |
| Total | | | | | |

In words (Rs.)

Note:

- GST extra
- Payment as per actual measurement
- All the above items must be exempted as per CPWD specification.

I/we accept the terms and conditions appended with the quotation.

Date:

Signature

Name and Address of the Quotationer.